



SCITUATE RAY PRECAST  
 120 CLAY PIT ROAD  
 MARSHFIELD, MA 02050  
 PHONE # 1-800-440-0009  
 FAX # 781-837-4320

CONTRACTOR:	JOB NAME:
-------------	-----------

DATE:	DRAWING: ST-3.5K-20	DRAWING BY: C. J. SCOTT
-------	---------------------	-------------------------

### 3,500 GALLON SEPTIC TANK

	FLOOR	VERT. FT	FLAT TOP
WEIGHT	10,000 lbs.	3,400 lbs.	13,000 lbs.
VOLUME		838 gal.	

DESIGN NOTES:

1. CONCRETE 5,000 PSI. @ 28 DAYS
2. HS-20-44 LOADING WITH 12" - 60" OF COVER
3. REINFORCING ASTM A-615 GRADE 60
4. CONST. JOINT TO HAVE MIN. 1" BUTYL SEALANT
5. EXTERIOR BITUMINOUS COATING AS REQUIRED



**NPCA**

Precast ... The Concrete Solution.

